| *Items of work.* | *Per.* | *Lower storey.* | *Upper storey.* |
|---|---|---|---|
| Cornice 1½′ deep | R. ft. | 718 | |
| Do 1′ do | Do | 2,708 | 2,598 |
| Do 7½″ do | Do | 1,510 | ... |
| Key stone moulding to arches | E | 51 | .. |
| Cut stone work for steps | S. ft. | 1,025 | .. |
| Slab stone templates | Do | 180 | .. |
| Do | Do | .. | 107 |
| Cast iron columns 13′ high 6″ at top and 7½″ at bottom | E | 6 | .. |
| Dental cornice 1½′ deep including architrave moulding | R. ft. | .. | 927 |
| Mangalore tile roofing | Sqr. | .. | 85 60 |
| Ionice columns with pedestal base and capital complete 19′ high | E | .. | 60 |
| Balustrading parapets | R. ft. | .. | 294 |
| Parapet at top of building | Do | .. | 786 |
| Terrace roofing | Sqr. | .. | 66·84 |
| Iron rod for truss, &c. | lbs. | .. | 68·55 |
| Central staircase | E | | 1 |
| End staircase | Do | | 2 |
| Servant staircase | Do | .. | 2 |
| Planking to footboard | S. ft. | .. | 2·45 |
| Teak wood work to footboard | C. ft. | .. | 10 |
| Hand railing do | R. ft. | .. | 64 |
| Cast iron ridging with crusting | Do | .. | 280 |
| Do ornamental ridging | Do | .. | 246 |
| Plank ceiling 1½″ for tower and side wards | Sqr. | .. | 70·22 |
| Pediment above ventilators | R. ft. | .. | 1,954 |
| For sham windows, imitation, balustrading and plinth moulding | Lump sum. | | |
| School of Arts tile roofing | Sqr. | .. | 77·52 |
| White and colour washing | Do | 387·0 | .. |
| Do do | Do | .. | 552 0 |
| Bamboo matting | Do | .. | 19·88 |
| Drainage pipe | Lump sum. | | |
| Cast iron shoes, clamps, plates, bolts, and other iron works for roofing of tower and trusses | Do | | |
| Cast iron ornamental finials | Do | | |
| Scaffolding for towers | Do | | |
| For ornamental moulding for superstructure on main pediment | Do | | |
| Cloth ceiling | Sqr. | .. | 17 60 |

## NOTICE.

The particular attention of contractors and others who intend submitting their tenders for the construction of the Administrative Block of the General Hospital at Bangalore is invited to the specification for work in the several parts of the walling available in the Executive Engineer's office, Bangalore division. The plans of the building may be seen at the Chief Engineer's office on all office days between the hours of 7 to 10 A. M.

2. Any further information as to details of work will be supplied on application at the Executive Engineer's office.

B. S. VENKATACHARIYAR, *Executive Engineer.*

## CHITALDRUG DIVISION.

*The 26th March* 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug division, up to 15th April 1897, for improving the District office at Chitaldrug. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1899.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chitaldrug between the hours of 7 A. M. and 11 A. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tenders for improving the District office at Chitaldrug :" in default of which tenders will be rejected.

5. The first acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond: in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

| *Description of work.* | *Unit of work.* | *Rate per unit.* |
|---|---|---|
| Dismantling the existing terrace, cornice, parapets, walls of main rooms and verandah, to the requisite level, &c.; also front verandah for introduction of large central archway, removing and re-fixing joists, including wood-oiling and raising of walls to proposed levels of joists. | S. ft. | 9,450 |
| Earthwork excavation | C. yd. | 436 |
| Concrete | C. ft. | 2,352 |
| Brick in chunam | „ | 10,597 |
| Do upper storey | „ | 20,591 |
| Archwork segmental | „ | 86 |
| Do flat | „ | 343 |
| Moulding brick in chunam | R. ft. | 95 |
| Dental cornice work | „ | 489 |
| Cornice work (light) | „ | 324 |
| Do (heavy) | „ | 411 |
| Plastering with chunam | Sqr. | 90·02 |
| Do upper storey | „ | 255·00 |
| Rolled steel girders | Tons. | 32·556 |
| Terrace floor and roof (pakka) | Sqr. | 163·19 |
| Iron railings | R. ft. | 171 |
| Alterations to front steps and opening out door to treasury and forming recess in front | Lump sum | |
| Stone slabs or bearing plates | S. ft. | 404 |
| Do upper storey | „ | 540 |
| Petty repairs to lower storey, such as white and color washings, painting doors, windows and repairs to floor | Lump sum | |
| Wooden staircases | Each | 2 |
| Carriage of steel girders from Bombay to Chitaldrug | Lump sum. | |
| Brick masonry columns with base and capitals, complete | „ | 19 |
| Parapet with pilasters, complete | R. ft. | 343 |
| Do do | „ | 314 |
| Imitation work in plaster in gables | Each | 2 |
| Teakwood work | C. ft. | 1,273 |
| Roofing with Mangalore tiles | Sqr. | 13·27 |
| Ridge tiles | R. ft. | 40 |
| Whitewashing | Sqr. | 197·42 |
| Colorwashing | „ | 58 |
| Teakwood doors | Each. | 30 |
| Do windows, small | „ | 14 |
| Do large windows | „ | 12 |
| Ventilators glazed | „ | 18 |
| Do small | „ | 12 |
| Screens | „ | 3 |
| Dias for Judges | „ | 2 |
| Prisoners' docks | „ | 2 |
| Witness boxes | „ | 2 |
| Terminals over centre of gable | „ | 1 |
| Do ends of gable | „ | 2 |
| Bamboo matting, outer rind | Sqr. | 56·69 |
| Iron work straps, &c., to trusses | Each. | 6 |
| Zinc pipes for drainage of roof | R. ft. | 760 |
| Carriage of steel rolled girders | Lump sum. | |

K. PRAHLADA RAO, *Executive Engineer.*

---

## HASSAN DIVISION.

*The 7th March* 1897.

WANTED—

A temporary Mutsaddi on Rs. 20 per mensem. None but Matriculates need apply.

Application should reach the undersigned on or before the 31st March 1897 with copies of testimonials if any.

A. S. NAGAVKAR, *Exec. Engr.*